

**Norway-Leikanger: Construction work**  
**OJ S 181/2016 20/09/2016**  
**Contract award notice**  
**Works**

**Directive 2004/18/EC**

**Section I: Contracting authority**

---

**I.1. Name and addresses**

Official name: Statens Vegvesen Region vest [The Norwegian Public Roads Administration, Western Region]

National registration number: 971032081

Postal address: Askedalen 4

Town: Leikanger

Postal code: 6863

Country: Norway

Contact person: Statens vegvesen Region vest, Fylkesavdeling Rogaland

For the attention of: Odd-Magnar Nerland

E-mail: [odd.nerland@vegvesen.no](mailto:odd.nerland@vegvesen.no)

Telephone: +47 90837052

**Internet address(es):**

Address of the buyer profile: <https://kgv.doffin.no/ctm/Supplier/CompanyInformation/Index/2687>

Electronic access to information: <https://kgv.doffin.no/ctm/Supplier/Documents/Folder/144081>

**I.2. Type of the contracting authority**

National or federal agency/office

**I.3. Main activity**

General public services

**I.4. Contract award on behalf of other contracting authorities**

The contracting authority is purchasing on behalf of other contracting authorities: no

**Section II: Object of the contract**

---

**II.1. Description**

**II.1.1. Title**

National Road 509 Sømmebakken — Sola school.

**II.1.2. Type of contract and place of performance or delivery**

Works

Execution

Main site or place of performance: National Road 509 Sømmebakken — Sola school.

NUTS code NO Norge

**II.1.3. Information about a framework agreement or a dynamic purchasing system (DPS)**

**II.1.4. Short description of the contract or purchase(s)**

The project national road 509 Sømmebakken — Sola school is a continuation from project national road 509 Sømmevågen — Flyplassvegen, and it is the start of transport corridor

West. The lot length is approx. 1 km, from profile -55-1030.

The main aim is to improve access to the port area in Risavika and Sola airport.

The project shall be constructed as a dual carriageway with a footpath on both sides. The total road width with the footpaths is approx. 34m.

There will be comprehensive relaying/new construction of water and sewage installations. The drainage from the road shall be led to a sedimentation basin/treatment basin before it is emitted to Havsford's inner basin area. There will also be major alterations for the cable departments, in particular Lyse, which also has important gas and high voltage lines in the area, which must be relaid.

Areas of archaeological interest have been uncovered along the planned road route, and these have been excavated. The project will be based on drawings and road models.

Main quantities:

- Mass removal of soil in the line: 13 500 m<sup>3</sup>
- Soil for the filling site: 15 400 m<sup>3</sup>
- Pipe ditches: 5 300 metres
- Cable ditches, including OPI channel: 4 520 m
- OPI channel, width approx. 1.75 m and height approx. 0.5 m: 1000 m
- Reinforcement layer, 22/120: 28 770 m<sup>3</sup>
- Base course, 0/32: 8000 m<sup>3</sup>
- Base course Ag16, 13 cm: 22 600 m<sup>2</sup>
- Asphalt cover, national road 509 wearing course, Ska and binder, Ab: 22 600 m<sup>2</sup>
- Asphalt cover other roads and foot/cycle paths, wearing course and binder Agb: 24 600 m<sup>2</sup>
- Noise reduction screens: 4 600 m<sup>2</sup>
- Kerbstones: 4 100 m
- Light masts: 190
- Railings, sicuro: 4400 m
- Demolition of asphalt cover: 20 000 m<sup>2</sup>

Subway and supporting walls:

- Casting: 1 850 m<sup>3</sup>
- Reinforcement: 305 tons
- Laid matter, blasted stone: 2 910 m<sup>3</sup>
- Filling, crushed matter: 7 300 m<sup>3</sup>
- Formwork: 4 350 m<sup>2</sup>

Sedimentation basin:

- Casting: 345 m<sup>3</sup>
- Reinforcement: 8.4 tons
- Excavation of uncompacted matter: 4 400 m<sup>3</sup>
- Laid matter, blasted stone: 1 500 m<sup>3</sup>
- Filling: 950 m<sup>3</sup>
- Formwork: 440 m<sup>2</sup>.

#### **II.1.5. CPV code(s)**

45000000 Construction work

#### **II.1.6. Information about the Government Procurement Agreement (GPA)**

The procurement is covered by the Government Procurement Agreement: yes

#### **II.2. Total value of the contract/lot**

##### **II.2.1. Total value of the contract/lot**

## Section IV: Procedure

---

### IV.1. Type of procedure

#### IV.1.1. Type of procedure

Open

### IV.2. Award criteria

#### IV.2.1. Award criteria

Lowest price

#### IV.2.2. Information about electronic auction

### IV.3. Administrative information

#### IV.3.1. File reference number attributed by the contracting authority

15/246978

#### IV.3.2. Previous publication concerning this procedure

##### Contract notice

Notice number in the OJ S: [2016/S 092-165569](#) of 13.5.2016

## Section V: Award of contract

---

Contract No: 1

Lot No: 1

- Lot title: National Road 509 Sømmebakken — Sola school

#### V.1. Date of conclusion of the contract

13.9.2016

#### V.2. Information about tenders

Number of tenders received: 6

#### V.3. Name and address of the contractor

Official name: Stangeland Maskin AS

National registration number: 935861330

Postal address: Sandnesvegen 80

Town: Sola

Postal code: 4050

Country: Norway

#### V.4. Information on value of the contract/lot

Initial estimated total value of the contract/lot:

Value: 87 716 723,14 NOK

excluding VAT

#### V.5. Information about subcontracting

The contract is likely to be subcontracted: no

## Section VI: Complementary information

---

### VI.1. Information about European Union funds

The procurement is related to a project and/or programme financed by European Union funds:  
no

**VI.2. Additional information**

**VI.3. Procedures for review**

**VI.3.1. Review body**

**VI.3.2. Review procedure**

**VI.3.3. Service from which information about the review procedure may be obtained**

**VI.4. Date of dispatch of this notice**

16.9.2016